



STUB PLUM.
TO 2ND FLR.
TO HAVE SHUT-OFF
VALVES

HOUSE TO BE ERRECTED AT
HARRISONBURG, VA
ROCKINGHAM COUNTY
20 LB. SNOW ZONE

THIS PRINT IS OK
TO BE BUILT

- NOTES:
1. HEAT LOSS WAS CALCULATED W/ R-19 INSULATION OR HEATED BSMT
 2. BUILDER IS RESPONSIBLE FOR PROVIDING A PROPERLY SIZED HEATING SYSTEM TO COVER A 30,000 BTU LOSS
 3. * - DENOTES ADDITIONAL COLUMN IN BASEMENT
 4. CLG. BEAM OVER LAUNDRY TO BE (2) 2"x10" SPF #2
 5. CLG. BEAM OVER LIV/DIN ROOMS TO BE (2) 1 1/2"x9 1/4" ML

6.
7. SIDING=22 1/2 SQ
8.
9. SHINGLES=18 SQ
10.



2830-CUSTOM CAPE 1st STORY FLOOR PLAN				
DRAWN BY: BSG/DGM	DATE: 4/25/02	SCALE: 1/4"=1'-0"	LAYER: SHL/FP1	FILE NO: A10005